

# You Want it When!?

## (Rapid Construction of the Backgate Interchange Embankments)

### MYRTLE BEACH, SOUTH CAROLINA



October 22 - 25, 2012



Presented By:

**Nicholas E. Harman, MS, PE**

# Regional Experience

Fantasy Harbour

2 Miles Away!

US 17/SC 707  
(Backgate)




# Fantasy Harbour



- 2 Miles North of Project
- New Alignment
- 35' Very Soft to Firm Clay
- Pockets of Loose Sand upper 15'
- Pockets of Loose sands Above Pee Dee Formation
- Pee Dee Formation (Top Elev. -20' msl)


# Fantasy Harbour Bridge

## West Abutment





# Fantasy Harbour Bridge East Abutment



# Fantasy Harbour



- Liquefaction – Loose Sands
- Embankments Unstable (Static/Seismic)
- Ground Improvement!!!
- 2 Year Embankment Construction Contract
- 2-3 Year Bridge Construction Contract

# Ground Improvement

- Stone Columns
  - Increase density of soil
  - Add shear resistance
  - Assist in decreasing settlement time
- Prefabricated Vertical Drains
  - Decrease time for settlement
  - Increase in shear strength gain rate
- Vertical Stage Construction
  - Allow for settlement
  - Increase in shear strength gain rate

# Staged Vertical Construction

- Embankment Construction Sequence
  - 15 feet; anticipated settlement 21 inches; waiting period ~6 months
  - Additional 10 feet; anticipated incremental settlement 22 inches, total settlement 43 inches; waiting period ~6 months
  - Final Grade achieved; anticipated incremental settlement 24 inches, total settlement 67 inches; final waiting period ~ 6 months

# Let's Return To US 17/ SC707 Interchange (Backgate)

South Bridge Approach Embankment

North Bridge Approach Embankment



SCDOT

Horry County  
Communities in Excellence


STV

US 17 Bypass at SC 707/Farrow Parkway  
Myrtle Beach, SC


Concept Rendering



# South Subsurface General Profile



# North Subsurface General Profile





# Geotechnical Challenges

- 30' to 60' - Soft to Firm Clay
- 5' to 10' Loose Sands
- Intermediate Medium Sands (253+00 to 256+00)
- Pee Dee Hard Clay Formation Elevation -70' msl
- Poor Site Subgrade (Bridging Required)
- Excessive Settlement – (Total & Differential)
- Short & Long-Term Embankment Instability
- Seismic Slope Instability (Liquefaction)

# Project Constraints



- Project Geometry and Layout
  - Existing Alignment
  - Limited R/W
  - Maintain all traffic movements & business access
- Limited Construction Staging Areas
- High Traffic Volume Combined
- Complex Traffic Control Staging Plan – Embankment construction occur primarily in Stages **2, 3, and 4**
- Construction Time Requirements – **3.5** years

# Rapid Embankment Construction



**Project  
Constraints**



**Geotechnical  
Challenges**






# Geotechnical Key Issues

- **Consolidation Settlement** - Total and Differential
- **Slope Instability** – During Construction and Seismic Event (Liquefaction)
- **Bridge Abutment Foundation Performance** - Extreme Events I and II

# Bridge Abutment Settlement (Normal Weight Fill)



# Geotechnical Construction Techniques




- **Lightweight Aggregate Borrow Material** – Reduce Magnitude of Settlement
- **Granular Surcharges / Prefabricated Vertical Drain (PVD)** – Increase Settlement and Rate of Settlement During Construction
- **Deep Soil Mixing** – Improve Seismic Slope Stability and Bridge Abutment Foundation Performance
- **Mechanically Stabilized Earth (MSE) Walls** – Required for Traffic Staging and Staying within R/W

# Granular Surcharge & Lightweight Aggregate Borrow


## Granular Surcharge Properties:

- $\phi = 32$  degrees
- Unit Weight: 125 pcf



## Lightweight Aggregate Properties:

- $\phi = 40$  degrees
- Short Term Unit Weight: 60 pcf
- Long Term Unit Weight: 70 pcf
- MSE Wall Backfill Properties



# Lightweight Aggregate Borrow (Rotary Kiln Produced)





# Lightweight Aggregate Borrow (Proposed New Material)



# Lightweight Aggregate Borrow (Proposed New Material Differences)

- Higher Fines Content
- Lighter Dry Unit Weight
- Total Unit Weight 15% Lighter
- High Absorption
- Gradation – Coarse Sand Instead of an Aggregate
- Compaction Verification Required

# Test Section (Dry)






# Test Section (Wet)




# Lightweight Aggregate Borrow Compaction Verification Challenges





# Compaction Control

- Laboratory Compaction Curves
- Moisture Content Varied Significantly for the same Dry Density
- Target 95% Max Dry Density = 43 pcf



# Compaction Control

- Conducted Test Section #2 to Evaluate Compaction Control Methods
- Compaction Control - Calibrated Nuclear Density Gauge, Sand Cone, 1 ft<sup>3</sup> Steel Box, and EDG.




# Compaction Control Calibrated Nuclear Gauge





# Granular Surcharge & Lightweight Aggregate Borrow





- Design Team Performed a Redesign
- Reduced the Lightweight Quantity by 15%
- Saved Horry County **\$2 Million**




# PVD Installation

$s = 3'$  and  $4'$




# PVD Installation





# PVD Installation Obstructions!!!




Predrilling










PVD Installation


# X-Section End Bent 1 (South Bridge Abutment, 237+50)




## Legend

- |   |   |  |
|---|---|--|
|  MSE Wall Type: BP                                     |  MSE Wall Type: BT |  Sand Drainage Layer (PVD Drainage) |
|  Light Weight Fill                                     |  MSE Wall Type: RT |  |
|  Deep Soil Mixing Lime-Cement Columns - Grout Design A |  MSE Wall Type: RP |  |
|  Deep Soil Mixing Lime-Cement Columns - Grout Design B |   |  |

# Settlement Transverse Profile (South Bridge Abutment – 237+83)




# Ramp A Settlement Measurements










# X-Section End Bent 7 (South Bridge Abutment, 250+26)

US 17 By-Pass Centerline




## Legend

- |   |   |  |
|---|---|--|
|  MSE Wall Type: BP                                     |  MSE Wall Type: BT |  Sand Drainage Layer (PVD Drainage) |
|  Light Weight Fill                                     |  MSE Wall Type: RT |  |
|  Deep Soil Mixing Lime-Cement Columns - Grout Design A |  MSE Wall Type: RP |  |




# Settlement Transverse Profile (North Bridge Abutment - 250+26)







# Ramp B Settlement Measurements



# Deep Soil Mixing Columns (Overlap – Block Pattern)

- Seismic Slope Stabilization – Shear Key
- Improved Performance of Bridge Abutment Foundations
- 2013






# Deep Soil Mixing Columns (Overlap – Block Pattern)

## Longitudinal DSM

## Bridge Abutment DSM

## Longitudinal DSM



# Traffic Control Stage 2



- MSE Walls
- Lightweight Aggregate Borrow Material
- 2', and 3' Granular Surcharge (Normal Weight)
- 3' and 4' Triangular Spacing PVD
- Geotechnical Instrumentation



# Construction Ramp A & B (PVD Installation)





# Construction Ramp A & B (MSE Wall Embankment Construction)



# Construction Ramp A & B (MSE Wall Embankment Construction)






# Construction Ramp A & B (MSE Wall Embankment Construction)



# Traffic Control Stage 2


Ramp C

Ramp D



- MSE Walls
- Lightweight Aggregate Borrow Material
- 1', 2', and 4' Granular Surcharge (Normal Weight)
- 3' and 4' Triangular Spacing PVD
- Geotechnical Instrumentation

# Traffic Control Stage 3 (Ramps A & B Completed)



Ramps C/D Construction  
(Under Construction -  
Stage 3)

Existing NB = Stage 3 SB

Constructed Ramps A/B  
(Completed – Stage 2)



# Construction Ramp C & D (Ramps A & B Completed)



# Traffic Control Stage 4

South Bridge Approach

Backgate Bridge

North Bridge Approach




- MSE Walls
- Lightweight Aggregate Borrow Material
- 1', 2', and 3' Granular Surcharge (Normal Weight)
- 3' Triangular Spacing PVD
- Geotechnical Instrumentation
- Bridge Abutment DSM  
(South 30' x 133' x 50'deep – North 30' x 141' x 70'deep )
- Longitudinal DSM (South 5' Wide / North 8' Wide)

# Project Construction Stages (North Abutment 252+01)


Ramp D  
Stage 3

Bridge Approach Embankment  
Stage 4


Ramp B  
Stage 2



# Bridge Abutment Construction (North Abutment – End Bent 7)



# Bridge Abutment Construction





# Geotechnical Instrumentation

## Settlement Monitoring

- 10 Settlement Plates (SP)
- 4 Magnetic Extensometer (ME)
- 12 VW Settlement Sensors (VWSS)
- 17 VW Piezometers (VWP)
- 2 VW Data Collection Centers (VWDCC)

## Slope Stability


- 6 Slope Indicator (SI)

# Settlement Plates





# VW Magnetic Extensometers



Pre-Assembled ME



Spider Magnet



Telescoping Section





# VW Settlement Sensors




# VW Settlement Sensor Data Collection






# VW Piezometers




# VW Device Connections



**VW Devices connected to 16-channel Board**

# Automated Data Collection



## VW Data Collection Center





# Data Collection Center

iSite Logger with Solar Controller  
Charging Battery



Inside DCC Enclosure  
& Solar Panel