

U.S. Department of Transportation

Federal Highway Administration

Geosynthetic Reinforced Soil Integrated Bridge System (GRS IBS) - Update and Case History

Southeastern Transportation Geotechnical Engineering Conference Charlotte, NC November 1, 2023


Daniel Alzamora, P.E. Senior Geotechnical Engineer



What is GRS IBS?

- Accelerated construction technique
- Utilizes compacted granular fill and geosynthetic reinforcement in alternating layers.











Design Process

- Updated Design and Construction Guidelines
- FHWA-HRT-17-080
- Revised for LRFD

Design and Construction Guidelines for Geosynthetic Reinforced Soil Abutments and Integrated Bridge Systems

PUBLICATION NO. FHWA-HRT-17-080











U.S. Department of Transportation
Federal Highway Administration

Research, Development, and Technology Turner-Fairbank Highway Research Center 6300 Georgetown Pike McLean, VA 22101-2296






GRS-IBS Long-Term Monitoring Projects

- Tiffin River, OH (2009)
- St. Lawrence County, NY (2013)
- Sheffield, MA (2014)














Long-Term Performance Monitoring of GRS Mini-Piers and Mini-Abutments at TFHRC

- Secondary settlement
- Open- vs. well-graded backfill
- Reinforcement strength
- Thermal interaction



- Secondary settlement
- Plane strain conditions (L/b)
- Shape effect
- Lateral pressure distributions




Source: FHWA





Bridge Approach Profiles

Comparison between GRS and conventional abutment




Source: FHWA





PR 2 (2013) - January 2020 Earthquake







PR 2 (2013) - January 2020 Earthquake




Source: PRHTA





January 2020 Earthquake



	M 4.5 in the seismic sequence						
	Magnitude	Date (m/d/y)	Lat (N)	Lon (W)	Depth (km)		
4.7	1/3/202	12/28/2019	17.9371	006	66.826	1 2	2
4.9	1/6/202	20	17.9	075	66.799	(6
5.8	1/6/202	20	17.8	17.8675		3 (5
4.6	1/7/202	20	17.9	645	66.8256	6 8	8
4.7	1/7/202	20	17.9	315	66.927	8	8
5.6	1/7/202	20	18.0	223	66.776	9	9
4.7	1/7/2020		17.9	128	66.6898	8 :	10
5	1/7/2020		17.9	418	66.6754	4 :	10
5.6	1/7/2020		17.8	919	66.7217	7 :	10
4.6	1/7/2020		17.9	206	66.767	:	10
5	1/7/2020		17.8	17.8685		9 :	10
6.4	1/7/20	20	17.9	578	66.811	3 (6
4.7	1/8/202	20	17.9	15	66.703	5 (5
5.2	1/10/20)20	17.9	35	66.883	9	9
4.6	1/11/20)20	17.9	423	66.8395	5 8	8
5.2	1/11/2020		17.8	238	66.794	1 :	10
5.9	1/11/2020		17.9	49	66.8508	8 5	5
4.8	1/11/2020		17.9	17.9923		6	4
	Data Irom the	ruerto Nico Seisifiic i	vetwork and	Jour			

Table 1: Summary of events greater than

Source: GEER Report



Federal Highway Administration







Geotechnical Reconnaissance of the January 7, 2020 M6.4 Southwest Puerto Rico Earthquake and Associated Seismic Sequence




Figure 6: Shaded relief of the southwestern region of Puerto Rico. Yellow line is the left lateral strike slip Punta Montalva fault. More than 2,000 red dots are seismic events between 28-Dec-2019 and 22-Jan-2020. White dots are the events larger than M5.0. Blue lines are the same faults as seen in Figure 4. Map from López et al., 2020b.






Figure 12: Intensity map showing isolines of PGA overlain on the generalized geologic map of the island. Values shown in the map are the accelerations in percentage of g and are the resultant of the maximum accelerations in the E-W and N-S directions. Image courtesy of Dr. C. Huertas of the UPRM-PRSMP.







PR 2 – 2013 vs 2020













PR 2 – 2013 vs 2020













PR 2 – 2013 vs 2020





Source: PRHTA





Recent Projects





WY – Sand Creek Rd (2016)





Image source: FHWA





RI – East Shore Expressway Bridge No 475 & McCormick Quarry Bridge No 476 (2016)



Image source: FHWA





CT – Project #100-178, North Haven, CT (2017)



Image source: CT DOT





AZ - I-40 over Meteor City Rd (2019)





Image source: FHWA





VT – Depot Rd over I-91, Hartland, VT (2020)



Source: Google Street View (September 2022)





AZ - I-40 A-1 Mountain Bridge (2022)





Source: AZ DOT

Source: Google Street View (April 2023)





OK – Grant County (2022)





Image source: OK DOT





MI – M-63 over I-196 (2019)



Source: Google Street View (July 2023)





Image source: MI DOT





MI - I-75 under Newport Road (2022)



Source: Google Street View (April 2023)





MI - I-75 under Nadeau Road (2022)




Source: Google Street View (August 2023)





MI - US-10 under Mackinaw Road (planned for 2024)




- MDOT has Successfully Completed Three 2-Span GRS-IBS Bridges
- We Continue to Improve the Design and Construction Process
 - Updates to Plans
 - Modify GRS Special Provisions
- Additional Wrapped Section Appears to Address the Issues
- Incorporated All Lessons Learned Into the Next Project
- Always Looking for Next GRS-IBS
- Midland County Road Commission has Built More Than 12 GRS-IBS Single Span

Image source: MI DOT











Image source: WV DOT










Image source: WV DOT





Proposal	Call Order Counties	Bidder ID	Bidder Name	Bid Amount		
1734099	1 RALEIGH	27-2000626	TRITON CONSTRUCTION, INC.	6,716,500.00	GRS IBS	
1734099	1 RALEIGH	83-0989025	ALL CONCRETE, INC.	7,385,527.72	GRS IBS	<mark>+10%</mark>
1734099	1 RALEIGH	55-0481221	MOUNTAINEER CONTRACTORS, INC.	8,109,719.58	MSE/piles	+21%
1734099	1 RALEIGH	55-0345840	VECELLIO & GROGAN, INC.	8,233,296.45	GRS IBS	<mark>+23%</mark>
1734099	1 RALEIGH	81-0626623	CLEARWATER CONSTRUCTION, INC.	8,392,000.00	MSE/piles	+25%
1734099	1 RALEIGH	55-0487806	ORDERS CONSTRUCTION COMPANY, INC.	8,919,984.67	MSE/piles	+33%

Image source: WV DOT

The unit price shall include in place the following: solid, hollow core, corner, and cap blocks, Reinforced Soil Foundation, geotextiles, coping, flashing, joint filler, foam blocks, spacer blocks, rebar dowels, concrete infill, and other similar items that are an incidental part of wall construction.

The unit price shall also include in place the items shown within the pay limits in the Plans as follows: granular backfill, excavation, embankment, sand leveling pads and fabric for separation. No separate measurement of these items shall be made.

626.9 – PAY ITEMS:

ADD THE FOLLOWING TO THE TABLE:

ITEM NUMBER		DESCRIPTION	UNIT
	626005-*	GRS-IBS MODULAR BLOCK RETAINING WALL	SF





28

Triton Construction, GRS IBS option:					
Total project cost \$6,716,500					
Total GRS IBS alternative	\$3,145,000				
GRS IBS Bid portion	\$1,094,150				
GRS IBS face quantity	15,050 sf				
Unit price	\$72.70/sf				

Average of 2 lowest Bids:	GRS IBS	MSE/Piles	Delta	
Total project cost	\$7,051,000	\$8,251,000	+\$1,200,000	+17%
Average costs (walls and piles)	\$1,081,000	\$1,261,965	+\$180,965	+17%
Total alternative costs	\$3,177,000	\$4,209,400	+\$1,032,400	+32%







Image source: FHWA












Image source: WV DOT
























Disclaimers

- Except for any statutes or regulations cited, the contents of this document do not have the force and effect of law and are not meant to bind the public in any way.
 This document is intended only to provide information regarding existing requirements under the law or agency policies.
- The approaches and methods discussed in the presentations are not Federal requirements unless otherwise stated. Some items may be required by State policy or specification.
- The U.S. Government does not endorse products, manufacturers, or outside entities. Trademarks, names, or logos appear in this presentation only because they are considered essential to the objective of the document. They are included for informational purposes only and are not intended to reflect a preference, approval, or endorsement of any one product or entity.







U.S. Department of Transportation

Federal Highway Administration

FHWA Resource Center

Office of Innovation Implementation

<u>Daniel Alzamora, P.E.</u> Senior Geotechnical Engineer FHWA – Resource Center

Daniel.alzamora@dot.gov

720-552-1600

